

Indian Lake Marina

Lakeview, Ohio



- > **Installation:** Tidewall TW80
- > **Linear Feet:** 1200 LF
- > **Sheet Lengths:** 8'
- > **Soil Conditions:** Sand/Clay
- > **Existing Wall:** None
- > **Contractor:** RJ Stone Company
- > **Design Engineer:** Jeff Stone
- > **Installation Method:** Bobcat Excavator with Plate Compactor

> **Project Details:**

The seawall was designed to protect a new marina being constructed on a canal connecting to Indian Lake. The sheet piling was installed dry, and then the channels were flooded and the project completed. In addition to the marina, the project contains an RV park and several permanent cabins.

